

ADDENDUM NO. 2
for
Cascade Science Lab Renovation

Schmidt Project No. 2008-046.CSL

Prepared For

Mill Creek Community School Corporation
6631 South County Road 200 West
Clayton, IN 46118-8904
317.539.9200 / FAX 317.539.9215

Prepared By

Schmidt Associates, Inc.
320 East Vermont Street
Indianapolis, Indiana 46204
317.263.6226 / FAX 317.263.6224



February 11, 2009

ADDENDUM NO. 2

CHANGES TO THE PROJECT MANUAL

Modifications described herein shall be incorporated in the Project Manual. All other Work shall remain unchanged.

Acknowledge receipt of this Addendum by inserting its number on the Bid Form. Failure to do so may subject the Bid to disqualification. This Addendum is part of the Contract Documents.

1.1 APPROVED MANUFACTURERS

Add the following as approved equals. Manufacturers listed below are subject to ALL requirements of the Contract Documents, including color selection where applicable.

- A. Section 123553 "Laboratory Casework",
 - 1. Wm. Hermann & Sons, for Wood Casework Alternate

1.2 CHANGES TO THE SPECIFICATIONS

- A. Division 00
 - 1. Section 001113 "Advertisement For Bids (Public)"
 - a. Modify Par.1.1.B.1 to read:
"1. February 18, 2009 at 2:00 PM"

CHANGES TO THE DRAWINGS

Modifications described herein shall be incorporated in the Drawings. All other Work shall remain unchanged.

1.3 A-SERIES DRAWINGS

- A. Sheet Number AC1A2
 - 1. Revise the last General Note in Reflected Ceiling Plan Notes to read as follows:
"See MEP & T Drawings for scope of ceiling removal and replacement in rooms below or adjacent to or along the utility route to the areas of renovation. Demolition of the existing ceilings and bulkheads may be required for the MEP & T work. Ceilings must be repaired to their condition equal to or better than prior to construction."

1.4 I-SERIES DRAWINGS

- A. Sheet Number I-401
 - 1. Drawing 1C: the three closed upper cabinets are alternates 2a and 2b.
 - 2. Drawing 3D: for base bid, the upper cabinets are as they are drawn. For alternates 2a and 2b delete the 2ft high upper cabinets and the large filler strip. Provide 36" high upper cabinets. Provide 1" filler between bulkhead and upper cabinets.
 - 3. Drawing 1E: for base bid, the upper cabinets are as they are drawn. For alternates 2a and 2b delete the 2ft high upper cabinets and the large filler strip. Provide 36" high upper cabinets. Provide 1" filler between bulkhead and upper cabinets.

- B. Sheet Number I-601

1. Room Finish Schedule
 - a. Delete all references to room number 103. No new finishes are required in this room.

1.5 E-SERIES DRAWINGS

- A. Sheet Number EP1A2
 1. Add the following general note:
“Routing of power conduits to science casework chases shall be routed adjacent to the plumbing in the first floor ceiling. Coordinate with Plumbing Contractor. If removal of hard surface and acoustical ceiling tile is required on the first floor to perform the utility work for the rooms above. All demoed ceilings must be repaired to condition equal to or better than you found it.”

END OF ADDENDUM NO. 2