

**Addendum #2**  
**Old Kings Road Elementary School Renovations and Additions**  
January 6, 2010

Addendum #2, to Drawings and Specifications dated November 23, 2009, as prepared by **SchenkelShultz** Architecture, 101 East Town Place, Suite 800, St. Augustine, Florida 32092

This Addendum #2 shall hereby be and become a part of the Contract Documents the same as if originally bound thereto.

The following clarifications, amendments, additions, revisions, changes and modifications change the original Contract Documents only in the amount and to the extent hereinafter specified and set forth in this Addendum #2.

-----

**CHANGES TO PROJECT MANUAL**

**ITEM NO. 1.: Section 01 33 00 Submittals**

**A.** **Revise** Paragraph 1.3 B. Construction Schedules to add the following:  
"2. Contractor Access to Site

- a. No work shall be performed on site when students are present during regular school hours, except by prior approval of the school Principal and FCSD Project Manager. Contractor access during school days after school hours shall be allowed.
- b. Contractor shall have site access during scheduled Holidays, Teacher Planning days, Spring Break days – Friday March 26, 2010 through Friday April 2, 2010 and Summer Break beginning - Thursday June 10, 2010.
- c. Date of Substantial Completion is Thursday, August 12, 2010
- d. Date of Final Completion is Thursday, August 18, 2010.
- e. No rain day time extensions shall be granted."

**ITEM NO. 2.: Section 07 41 13 Preformed Metal Roofing**

**A.** **Add** to the list of approved manufacturers in paragraph 2.1 A.:  
"5. Series 2500, Englert, Inc., Tampa, Florida."

**ITEM NO. 3.: Section 08 51 13 Aluminum Windows**

**A.** **Revise** 1.3 C. from 'AAMA AW-50' to read: "...AAMA HC 60..."

**B.** **Revise** 2.2 B. to delete: "...with integral structural polyurethane thermal break..."

**ITEM NO. 4.: Section 10 14 00 Identifying Devices**

**A.** **Add** Paragraph 2.3 to read:

"2.3 EXTERIOR SIGNAGE

- A. Provide one exterior sign in compliance with Florida Administrative Code Section 69A-60.008 (Florida Fire Prevention Code) as follows – 8" x 8" Maltese Cross symbol with the letter 'R' in the center. Finish: bright reflective red." Mount sign on face of pilaster to left of entry door. Mount bottom of sign at 54" AFF."

**ITEM NO. 5.: Section 10 73 26 Aluminum, Walkway Canopy**

**A.** **Add** to the list of approved manufacturers in paragraph 2.1 A.:  
"7. Custom Screens and Architectural Products."

**CHANGES TO DRAWINGS**

ITEM NO. 6.: Sheet C3.0

- A. Revise Note: 'see plumbing plan for roof drain downspouts to connect typ.', to read: "See Architectural Sheet AN100 for locations of roof and canopy drain downspouts. Manifold roof drains with 8" PVC piping and manifold canopy system drains with 4" PVC piping."
- B. Concrete sidewalk demolition: Add note: "Demolition of existing concrete sidewalks within the areas on sheet C3.0 adjacent to the new building addition that are shown as stippled (poche'd) are IN CONTRACT."

ITEM NO. 7.: Sheet C4.0

- A. Note: The six inch Fire Line Service that is indicated on sheet C4.0 Utility Plan previously issued in Addendum No. 1 (Item #12) as 'For Reference Only' shall be revised to read: "Fire Line Service from Tee at existing backflow preventer to inside Bldg #1 is IN CONTRACT."
- B. Add note where Fire Line enters Bldg #1, to read: "Fire Line shall turn up outside of exterior wall and footing and enter building above existing finished floor elevation."

ITEM NO. 8.: Sheet AN711

- A. Revise Section 2/AN711 to relocate note 'WET Column from Roof, Above" from two locations at front columns to new locations at the two pilaster columns adjacent to the building – as shown on sheet AN100.

End of Addendum #2

G:\092000\0920126 Old Kings ES Admin-Renos & Addn\Project Files\Addendum\Add 2\Addendum No2\_01-06-10.doc